

Specification For Segmental Retaining Wall Systems Versa-Lok[®] Mosaic

PART 1: GENERAL

1.01 Description

- A. Work includes furnishing and installing segmental retaining wall (SRW) units to the lines and grades designated on the project's final construction drawings or as directed by the Architect/Engineer. Also included is furnishing and installing appurtenant materials required for construction of the retaining wall as shown on the construction drawings.

1.02 Reference Standards

A. Segmental Retaining Wall Units

1. ASTM C 1372 - Standard Specification for Segmental Retaining Wall Units
2. ASTM C 140 - Standard Test Methods of Sampling and Testing Concrete Masonry Units

B. Geosynthetic Reinforcement

1. ASTM D 4595 - Tensile Properties of Geotextiles by the Wide-Width Strip Method
2. ASTM D 5262 - Test Method for Evaluating the Unconfined Creep Behavior of Geosynthetics
3. GRI:GG1 – Single-Rib Geogrid Tensile Strength
4. GRI:GG5 - Geogrid Pullout

C. Soils

1. ASTM D 698 - Moisture Density Relationship for Soils, Standard Method
2. ASTM D 422 - Gradation of Soils
3. ASTM D 424 - Atterberg Limits of Soil

D. Drainage Pipe

1. ASTM D 3034 - Specification for Polyvinyl Chloride (PVC) Plastic Pipe
2. ASTM D 1248 - Specification for Corrugated Plastic Pipe

E. Engineering Design

1. "NCMA Design Manual for Segmental Retaining Walls," Second Edition

- F. Where specifications and reference documents conflict, the Architect/Engineer shall make the final determination of applicable document.

1.03 Submittals

- A. Materials Submittals: The Contractor shall submit manufacturers' certifications two weeks prior to start of work stating that the SRW units and geosynthetic reinforcement meet the requirements of Section 2 of this specification.

- B. Design Submittal: The Contractor shall submit two sets of detailed design calculations and final retaining wall plans for approval at least two weeks prior to the beginning of wall construction. All calculations and drawings shall be prepared and sealed by a professional Civil Engineer (P.E.) – (Wall Design Engineer) experienced in SRW design and licensed in the state where the wall is to be built.

1.04 Delivery, Storage and Handling

- A. Contractor shall check materials upon delivery to assure that specified type and grade of materials have been received and proper color and texture of SRW units have been received.
- B. Contractor shall prevent excessive mud, wet concrete, epoxies and like materials that may affix themselves from coming in contact with materials.
- C. Contractor shall store and handle materials in accordance with manufacturer's recommendations.
- D. Contractor shall protect materials from damage. Damaged materials shall not be incorporated into the retaining wall.

PART 2: MATERIALS

2.01 Segmental Retaining Wall Units

- A. SRW units shall be machine-formed, Portland cement concrete blocks specifically designed for retaining wall applications. SRW units currently approved for this project are:

VERSA-LOK Mosaic Retaining Wall System that includes three unit types: VERSA-LOK Standard units, VERSA-LOK Cobble units and VERSA-LOK Accent units, as manufactured by R.I. Lampus Company.
- B. Color of SRW units shall be _____.
- C. Finish of SRW units shall be split-face.
- D. SRW unit faces shall be of straight geometry.
- E. SRW unit heights shall be both 4 and 6 inches.
- F. SRW units shall be designed to stack in "panels" 10 inches high by 24 inches wide consisting of the three SRW unit types that can be stacked in varied patterns to create a random look.
- G. SRW units (not including aggregate fill in unit voids) shall provide a minimum weight of 105 psf wall face area.
- H. SRW units shall be solid throughout the full depth of the unit.

- I. SRW units shall have a depth (front face to rear) to height ratio of 2:1, minimum.
- J. SRW units shall be interlocked with connection pins, which provide $\frac{3}{4}$ -inch setback from the unit below (4- and 6-inch high units are stacked alternately, yielding an overall 8.5-degree cant from vertical).
- K. SRW units shall be capable of being erected with the horizontal gap between adjacent units not exceeding $\frac{1}{8}$ inch.
- L. SRW units shall be capable of being installed with a continuous, level course at every 10 inches of height so geosynthetic reinforcement layers can be placed level within the wall face.
- M. SRW units shall be capable of providing overlap of units on each successive course of a corner so that walls meeting at corner are interlocked and continuous. SRW units that require corners to be mitered shall not be allowed.
- N. SRW units shall be sound and free of cracks or other defects that would interfere with the proper placing of the unit or significantly impair the strength or permanence of the structure. Cracking or excessive chipping may be grounds for rejection. Units showing cracks longer than $\frac{1}{2}$ inch shall not be used within the wall. Units showing chips visible at a distance of 30 feet from the wall shall not be used within the wall.
- O. Concrete used to manufacture SRW units shall have a minimum 28 days compressive strength of 3,000 psi and a maximum moisture absorption rate, by weight, of 8% as determined in accordance with ASTM C140. Compressive strength test specimens shall conform to the saw-cut coupon provisions of ASTM C140.
- P. SRW units' molded dimensions shall not differ more than $\pm \frac{1}{8}$ inch from that specified, in accordance with ASTM C1372.

2.02 Segmental Retaining Wall Unit Connection Pins

- A. SRW units shall be interlocked with VERSA-Tuff Snap-Off connection pins, 6.8 inches in length, with a section that can snap off, yielding a 4.6-inch long pin. The pins shall consist of glass-reinforced nylon made for the expressed use with the SRW units supplied.

2.03 Geosynthetic Reinforcement

- A. Geosynthetic reinforcement shall consist of geogrids or geotextiles manufactured as a soil reinforcement element. The manufacturers/suppliers of the geosynthetic reinforcement shall have demonstrated construction of similar size and types of segmental retaining walls on previous projects.

The geosynthetic type must be approved one week prior to bid opening. Geosynthetic types currently approved for this project are:

VERSA-Grid Geogrids

- B. The type, strength and placement location of the reinforcing geosynthetic shall be as determined by the Wall Design Engineer, as shown on the final, P.E.-sealed retaining wall plans.

2.04 Leveling Pad

- A. Material for leveling pad shall consist of compacted sand, gravel, or combination thereof (USCS soil types GP, GW, SP, & SW) and shall be a minimum of 6 inches in depth. Lean concrete with a strength of 200-300 psi and 3 inches thick maximum may also be used as a leveling pad material. The leveling pad should extend laterally at least a distance of 6 inches from the toe and heel of the lowermost SRW unit.

2.05 Drainage Aggregate

- A. Drainage aggregate shall be angular, clean stone or granular fill meeting the following gradation as determined in accordance with ASTM D422

<u>Sieve Size</u>	<u>Percent Passing</u>
1 inch	100
3/4 inch	75-100
No. 4	0-60
No. 40	0-50
No. 200	0-5

2.06 Drainage Pipe

- A. The drainage collection pipe shall be a perforated or slotted PVC, or corrugated HDPE pipe. The drainage pipe may be wrapped with a geotextile to function as a filter.
- B. Drainage pipe shall be manufactured in accordance with ASTM D 3034 and/or ASTM D 1248.

2.07 Reinforced (Infill) Soil

- A. The reinforced soil material shall be free of debris. Unless otherwise noted on the final, P.E.-sealed, retaining wall plans prepared by the Wall Design Engineer, the reinforced material shall consist of the inorganic USCS soil types GP, GW, SW, SP, SM, meeting the following gradation, as determined in accordance with ASTM D422:

<u>Sieve Size</u>	<u>Percent Passing</u>
4 inch	100
No. 4	20-100
No. 40	0-60
No. 200	0-35

- B. The maximum particle size of poorly-graded gravels (GP) (no fines) should not exceed 3/4 inch unless expressly approved by the Wall Design Engineer and the long-term

design strength (LTDS) of the geosynthetic is reduced to account for additional installation damage from particles larger than this maximum.

C. The plasticity of the fine fraction shall be less than 20.

PART 3: DESIGN PARAMETERS

3.01 Soil

A. The following soil parameters, as determined by the Owner's Geotechnical Engineer shall be used for the preparation of the final design:

	Unit Weight (γ) (pcf)	Internal Friction Angle (ϕ) (degrees)	Cohesion (c)
Reinforced Fill	_____	_____	0
Retained Soil	_____	_____	0
Foundation Soil	_____	_____	_____

(If internal friction angles are not available for the above section, the specifier can provide the USCS soil type classification for the reinforced, retained, and foundation soils and/or attach the geotechnical investigation report for this project.)

B. Should the actual soil conditions observed during construction differ from those assumed for the design, design shall be reviewed by the Wall Design Engineer at the Owner's Geotechnical Engineer's direction.

3.02 Design

A. The design analysis for the final, P.E.-sealed retaining wall plans prepared by the Wall Design Engineer shall consider the external stability against sliding and overturning, internal stability and facial stability of the reinforced soil mass and shall be in accordance with acceptable engineering practice and these specifications. The internal and external stability analysis shall be performed in accordance with the "NCMA Design Manual for Segmental Retaining Walls," using the recommended minimum factors of safety in this manual.

B. External stability analysis for bearing capacity, global stability, and total and differential settlement shall be the responsibility of the Owner and the Owner's Geotechnical Engineer. Geotechnical Engineer shall perform bearing capacity, settlement estimates, and global stability analysis based on the final wall design provided by the Wall Design Engineer and coordinate any required changes with Wall Design Engineer.

C. While vertical spacing between geogrid layers may vary, it shall not exceed 2.0 feet maximum in the wall design.

D. The geosynthetic placement in the wall design shall have 100% continuous coverage parallel to the wall face. Gapping between horizontally adjacent layers of geosynthetic (partial coverage) will not be allowed.

PART 4: CONSTRUCTION

4.01 Inspection

- A. The Owner or Owner's Representative is responsible for verifying that the Contractor meets all the requirements of the specification. This includes all submittals for materials and design, qualifications, and proper installation of wall system.
- B. Contractor's field construction supervisor shall have demonstrated experience and be qualified to direct all work at the site.

4.02 Excavation

- A. Contractor shall excavate to the lines and grades shown on the project grading plans. Contractor shall take precautions to minimize over-excavation. Over-excavation shall be filled with compacted infill material, or as directed by the Engineer/Architect, at the Contractor's expense.
- B. Contractor shall verify location of existing structures and utilities prior to excavation. Contractor shall ensure all surrounding structures are protected from the effects of wall excavation. Excavation support, if required, is the responsibility of the Contractor.

4.03 Foundation Preparation

- A. Following the excavation, the foundation soil shall be examined by the Owner's Engineer to assure actual foundation soil strength meets or exceeds the assumed design bearing strength. Soils not meeting the required strength shall be removed and replaced with infill soils, as directed by the Owner's Engineer.
- B. Foundation soil shall be proof-rolled and compacted to 95% standard Proctor density and inspected by the Owner's Engineer prior to placement of leveling pad materials.

4.04 Leveling Pad Construction

- A. Leveling pad shall be placed as shown on the final, P.E.-sealed retaining wall plans with a minimum thickness of 6 inches. The leveling pad should extend laterally at least a distance of 6 inches from the toe and heel of the lowermost SRW unit.
- B. Granular leveling pad material shall be compacted to provide a firm, level bearing surface on which to place the first course of units. Well-graded sand can be used to smooth the top 1/4 inch to 1/2 inch of the leveling pad. Compaction will be with mechanical plate compactors to achieve 95% of maximum standard Proctor density (ASTM D 698).

4.05 SRW Unit Installation

- A. All SRW units shall be installed at the proper elevation and orientation as shown on the final, P.E.-sealed wall plans and details on the construction plans, or as directed by the Wall Design Engineer. The SRW units shall be installed in general accordance with the manufacturer's recommendations. The specifications and drawings shall govern in any

conflict between the two requirements.

- B. For ease of installation, generally the base course of SRW units shall be all 6-inch-high Standard units placed on the leveling pad. The units shall be leveled side-to-side, front-to-rear and with adjacent units, and aligned to ensure intimate contact with the leveling pad. The base course is the most important to ensure accurate and acceptable results. No gaps shall be left between the front of adjacent units. Alignment may be done by means of a stringline or offset from baseline to the back of the units. Placing panels of Mosaic directly on the leveling pad is also acceptable. In this case, the entire 10-inch-high course of panels must be installed before the level and alignment can be checked.
- C. All excess debris shall be cleaned from top of units.
- D. Mosaic panels shall be placed on the units below. Each panel shall be installed completely prior to installing horizontally adjacent panels. Each Mosaic panel shall be 10 inches high by 24 inches wide, consisting of one Standard unit, one Cobble unit, and two Accent units. With each adjacent panel, the units at the bottom of the panels should be alternated from 4-inch-high units to 6-inch-high units. As an example, one panel shall have Accent units at the base of the panel with Standard and Cobble units on top. The next adjacent panel shall have the Standard and Cobble units at the bottom and Accent units on top. The order of the Cobble and Standard units shall be randomly mixed within the panels to avoid a repetitive pattern. The entire length of each 10-inch-high course of panels shall be installed before starting the next course of panels.
- E. Each unit in a Mosaic panel shall be pinned to the units below in the following manner: Two VERSA-Tuff connection pins shall be inserted through the pin holes of each unit into receiving slots in units below, creating an approximate $\frac{3}{4}$ -inch setback from the unit below. Pins shall be fully seated in the pin slot below. When pinning 4-inch-high Accent units, the top 2 inches of the 6.8-inch pin will initially extend above the Accent unit. The top of the pin shall be snapped off by hitting the top of the pin from the side. Once pinned, the units shall be pushed forward to remove any looseness in the unit-to-unit connection.

Prior to placement of next course of panels, the level and alignment of the units shall be checked and corrected where needed.
- F. The next course of panels shall be placed so that it is staggered at least 4 inches from the vertical joints between the panels below. The patterns in the Mosaic panels generally shall not line up with the course below. The bond of the panels shall be varied on subsequent courses to create a random look.
- G. Layout of curves and corners shall be installed in accordance with the wall plan details or in general accordance with SRW manufacturer's installation guidelines. Walls meeting at corners shall be interlocked by overlapping successive courses of panels. Special corner panels shall be installed such that both sides of the corner panels vertically align the upper and lower units to create 10-inch-high joints to butt against adjacent regular Mosaic panels. For each course of panels, the corner panels shall be installed first, then regular panels installed out from the corners.

- H. Procedures C. through G. shall be repeated until reaching top of wall units, just below the height of the cap units. Geosynthetic reinforcement, drainage materials and reinforced backfill shall be placed in sequence with unit installation as described in Section 4.06, 4.07 and 4.08.

4.06 Geosynthetic Reinforcement Placement

- A. All geosynthetic reinforcement shall be installed at the proper elevation and orientation as shown on the final P.E.-sealed retaining wall plan profiles and details, or as directed by the Wall Design Engineer.
- B. At the elevations shown on the final plans, (after the units, drainage material and backfill have been placed to this elevation) the geosynthetic reinforcement shall be laid horizontally on compacted infill and on top of the concrete SRW units, to within 1 inch of the front face of the unit below. Embedment of the geosynthetic in the SRW units shall be consistent with SRW manufacturer's recommendations. Correct orientation of the geosynthetic reinforcement shall be verified by the Contractor to be in accordance with the geosynthetic manufacturer's recommendations. The highest-strength direction of the geosynthetic must be perpendicular to the wall face.
- C. Geosynthetic reinforcement layers shall be one continuous piece for their entire embedment length. Splicing of the geosynthetic in the design-strength direction (perpendicular to the wall face) shall not be permitted. Along the length of the wall, horizontally adjacent sections of geosynthetic reinforcement shall be butted in a manner to assure 100% coverage parallel to the wall face.
- D. Tracked construction equipment shall not be operated directly on the geosynthetic reinforcement. A minimum of 6 inches of backfill is required prior to operation of tracked vehicles over the geosynthetic. Turning should be kept to a minimum. Rubber-tired equipment may pass over the geosynthetic reinforcement at slow speeds (less than 5 mph).
- E. The geosynthetic reinforcement shall be free of wrinkles prior to placement of soil fill. The nominal tension shall be applied to the reinforcement and secured in place with staples, stakes or by hand tensioning until reinforcement is covered by 6 inches of fill.

4.07 Drainage Materials

- A. Drainage aggregate shall be installed to the line, grades and sections shown on the final P.E.-sealed retaining wall plans. Drainage aggregate shall be placed to the minimum thickness shown on the construction plans between and behind units (a minimum of 1 cubic foot for each exposed square foot of wall face unless otherwise noted on the final wall plans).
- B. Drainage collection pipes shall be installed to maintain gravity flow of water outside the reinforced-soil zone. The drainage collection pipe shall daylight into a storm sewer or along a slope at an elevation below the lowest point of the pipe within the aggregate drain.

4.08 Backfill Placement

- A. The reinforced backfill shall be placed as shown in the final wall plans in the maximum compacted lift thickness of 10 inches and shall be compacted to a minimum of 95% of standard Proctor density (ASTM D 698) at a moisture content within 2% of optimum. The backfill shall be placed and spread in such a manner as to eliminate wrinkles or movement of the geosynthetic reinforcement and the SRW units.
- B. Only hand-operated compaction equipment shall be allowed within 3 feet of the back of the wall units. Compaction within the 3 feet behind the wall units shall be achieved by at least three passes of a lightweight mechanical tamper, plate, or roller.
- C. At the end of each day's operation, the Contractor shall slope the last level of backfill away from the wall facing and reinforced backfill to direct water runoff away from the wall face.
- D. At completion of wall construction, backfill shall be placed level with final top of wall elevation. If final grading, paving, landscaping and/or storm drainage installation adjacent to the wall is not placed immediately after wall completion, temporary grading and drainage shall be provided to ensure water runoff is not directed at the wall nor allowed to collect or pond behind the wall until final construction adjacent to the wall is completed.

4.09 SRW Caps

- A. SRW caps shall be properly aligned and glued to underlying units with VERSA-LOK adhesive, a flexible, high-strength concrete adhesive. Rigid adhesive or mortar are not acceptable.
- B. Caps shall overhang the top course of units by 3/4 inch to 1 inch. Slight variation in overhang is allowed to correct alignment at the top of the wall.

4.10 Construction Adjacent to Completed Wall

- A. The Owner or Owner's Representative is responsible for ensuring that construction by others adjacent to the wall does not disturb the wall or place temporary construction loads on the wall that exceed design loads, including loads such as water pressure, temporary grades, or equipment loading. Heavy paving or grading equipment shall be kept a minimum of 3 feet behind the back of the wall face. Equipment with wheel loads in excess of 150 psf live load shall not be operated within 10 feet of the face of the retaining wall during construction adjacent to the wall. Care should be taken by the General Contractor to ensure water runoff is directed away from the wall structure until final grading and surface drainage collection systems are completed.

END OF SECTION